



# **ADDENDUM No. 2**

**Date:** February 4, 2014

**Project:** Piqua Power System  
Containment Pads

## **ADDENDUM ACKNOWLEDGEMENT**

**BIDDER hereby acknowledges receipt of:**

**ADDENDUM No. 2**

**Date: February 4, 2014**

**Consisting of: 1**

**and confirm that the provisions of said**

**addendum have been incorporated into**

**the bid forms for the**

**PIQUA POWER SYSTEM  
UTILITY SERVICE CENTER**

**and agree that we have included the provisions**

**of said addendum in our bid**

---

**Company:**

---

**By:** \_\_\_\_\_

**Date:** \_\_\_\_\_

Piqua Power System  
Containment Pads  
**Addendum #2**  
February 4, 2014

Bidders shall note the following changes and additional information, which are hereby made part of the Contract Documents:

**CLARIFICATIONS:**

- 1) Storm piping clarification: 12" RCP is to be used as shown on the drawings from CB#17 to the new CB which is to be installed by the City of Piqua. The other 10" piping that is not specified on the drawings is to be 10" HDPE (high density polyethylene) smooth interior piping. HDPE pipe to be installed per manufacturer's recommendations with gasketed bell and spigot joints.
- 2) Drawing C.1 - There is a note on the east side of the project that reads "new 6" curb (Detail 10/C.4)". This note does not apply to this project – please disregard. The only new curbing is at the Southwest corner of the lot (noted as "new curb detail 2/C.1) adjacent to the existing grass area (grass area also noted as the "temporary gravel storage area").
- 3) Light Poles clarification – Light poles and anchor bolts are to be provided by the City of Piqua. Anchor bolts shall be installed by the Bid Package 2 Concrete Contractor. Concrete pole bases to be excavated and installed by Bid Package 2 Concrete Contractor. Light poles to be installed by the City of Piqua.
- 4) Bid Extension: Bids are now due Friday, Feb 7, at 3:00 pm.

**ATTACHMENTS:**

- 1) None